

PROJECT DATA

APPLICATION TYPE	Paving
PARTICIPANTS	
OWNER	FedEx
ENGINEER	Saad Development Corporation
GENERAL CONTRACTOR	JMD Construction
CONCRETE CONTRACTOR	JAG Contractors
READY-MIX CONCRETE SUPPLIER	Campbell Concrete
FIBER SUPPLIER	FiberForce
FIBER TYPE & DOSAGE	FiberForce 750 1.5" length 5 pounds per cubic yard

DETAILS

VOLUME	3500 cubic yards
PROJECT DATE	June 2018



The FedEx project consisted of 10" thick 4000 psi concrete with #6 rebar at 12" o.c. each way along with 5 pounds per yard of the FiberForce 750 macro fiber. Fibers were used along with rebar to prevent cracking in heavy traffic FedEx ground facility paving. The contractor finished the concrete by hand and by using a vibratory screed. Both the GC and concrete contractor were happy with the finish, workability, and final product.

